

AD-A157 558


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
BLODGETT DAM (VT 0011 (U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV OCT 80


1/2

UNCLASSIFIED

F/G 13/13

NL





MICROCOPY RESOLUTION TEST CHART
NBS-1963-A

①

AD-A157 558

CONNECTICUT RIVER BASIN
BRADFORD, VERMONT

BLODGETT DAM
VT 00117

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM



DTIC
ELECTE
JUL 19 1985
S D
H G

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154

OCT, 1980

DISTRIBUTION STATEMENT A
Approved for public release
Distribution Unlimited

DTIC FILE COPY

85 7 01 158

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM	
1. REPORT NUMBER VT 00117	2. GOVT ACCESSION NO. AD-A157558	3. RECIPIENT'S CATALOG NUMBER	
4. TITLE (and Subtitle) Blodgett Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT	
		6. PERFORMING ORG. REPORT NUMBER	
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		8. CONTRACT OR GRANT NUMBER(s)	
9. PERFORMING ORGANIZATION NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS	
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		12. REPORT DATE October 1980	
		13. NUMBER OF PAGES 67	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report) UNCLASSIFIED	
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE	
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED			
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)			
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.			
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Connecticut River Basin Bradford, VT. Roaring Brook			
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The dam is a zoned earthfill embankment about 29 ft. high and 714 ft. long. The dam is considered to be in fair condition. The dam is small in size with a significant hazard potential. There are a few recommendations and remedial measures which should be undertaken by the owner.			

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
424 TRAPELO ROAD
WALTHAM, MASSACHUSETTS 02254

REPLY TO
ATTENTION OF:
NEDED

MAR 06 1981

Honorable Richard A. Snelling
Governor of the State of Vermont
State Capitol
Montpelier, Vermont 05602

Dear Governor Snelling:

Inclosed is a copy of the Blodgett Dam (VT-00117) Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Department of Water Resources, the cooperating agency for the State of Vermont. In addition, a copy of the report has also been furnished the owner, Mr. Putnam W. Blodgett, Bradford, Vermont 05033.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Department of Water Resources for your cooperation in carrying out this program.

Sincerely,

C. E. EDGAR, III
Colonel, Corps of Engineers
Division Engineer

Incl
As stated

BLODGETT DAM

VT 00117

CONNECTICUT RIVER BASIN

BRADFORD, VERMONT

PHASE I INSPECTION REPORT

NATIONAL DAM INSPECTION PROGRAM

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A/	



BRIEF ASSESSMENT
PHASE I INSPECTION REPORT
NATIONAL PROGRAM OF INSPECTION OF DAMS.

Identification Number:	VT 00117
Name of Dam:	BLODGETT DAM
Town:	BRADFORD
County and State:	ORANGE COUNTY, VERMONT
Stream:	ROARING BROOK
Date of Inspection:	AUGUST 5, 1980


The dam, constructed in 1965, is a zoned earthfill embankment approximately 29 feet high and 714 feet long, including an 80 foot long overflow spillway founded in bedrock located to the left of the dam. The spillway contains a concrete crest wall, 15 feet of which is lower than the remaining 65 feet and constitutes the primary spillway. The right side of the downstream spillway channel is an earthen training wall protected by riprap. The upstream slope of the main dam is inclined at 3 horizontal to 1 vertical; the downstream slope is inclined at 2½ horizontal to 1 vertical and is equipped with a drainage system. The manually operated, gated low level outlet, located about 180 feet from the right abutment, is an 18 inch diameter corrugated metal pipe. The gate is reported to be operable.


The dam impounds a recreational pool in the lower watershed of Roaring Brook, and the discharge flows in an easterly direction approximately 3700 feet to its confluence with the Connecticut River. The impoundment is 1100 feet in length with a surface area of 14 acres. Normal storage capacity is 100 acre-feet.

Based upon the visual inspection and the review of available data regarding this facility, the dam is considered to be in FAIR condition. The considerable evidence of seepage noted downstream of the dam is not considered evidence of structural instability but should be monitored for changes in quality or quantity.

In accordance with the Corps of Engineers Guidelines and the size (SMALL) and hazard (SIGNIFICANT) of the dam, the Test Flood selected for use in the analysis was equivalent to the 100 year recurrence flood. Peak inflow to the impoundment is 1600 cfs; routed peak outflow from the dam 1470 cfs with the water elevation 4.2 feet over the spillway crest, or 6.8 feet below the top of the dam. The spillway capacity is 8950 cfs or 609% of the routed Test Flood outflow.

It is recommended that the owner retain a qualified registered engineer to design a seepage collection system that would permit measurement of the seepage observed at the downstream toe of the embankment, and to oversee removal of trees and root systems from the embankment and channel areas. This and remedial measures which are discussed in Section 7 should be instituted within one year of the owner's receipt of this report.



Stephen D. Murray, P.E.
Project Manager
James W. Sewall Company



This Phase I Inspection Report on Blodgett Dam (VT-00117) has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgement and practice, and is hereby submitted for approval.



ARAMAST MAHTESIAN, MEMBER
Geotechnical Engineering Branch
Engineering Division




CARNEY M. TERZIAN, MEMBER
Design Branch
Engineering Division



JOSEPH W. FINEGAN, JR., CHAIRMAN
Water Control Branch
Engineering Division

APPROVAL RECOMMENDED:



JOE B. FRYAR
Chief, Engineering Division

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

The Phase I Investigation does not include an assessment of the need for fences, gates, no-trespassing signs, repairs to existing fences and railings and other items which may be needed to minimize trespass and provide greater security for the facility and safety to the public. An evaluation of the project for compliance with OSHA rules and regulations is also excluded.

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
Letter of Transmittal	
Brief Assessment	
Review Board Page	
Preface	i
Table of Contents	ii-iv
Overview Photo	v
Location Map	vi

REPORT

1. PROJECT INFORMATION	1-1
1.1 General	1-1
a. Authority	1-1
b. Purpose of Inspection Program	1-1
1.2 Description of Project	1-1
a. Location	1-1
b. Description of Dam and Appurtenances	1-1
c. Size Classification	1-2
d. Hazard Classification	1-2
e. Ownership	1-2
f. Operator	1-2
g. Purpose of Dam	1-2
h. Design and Construction History	1-2
i. Normal Operational Procedures	1-3
1.3 Pertinent Data	1-3
a. Drainage Area	1-3
b. Discharge at Dam Site	1-3
c. Elevation	1-3
d. Reservoir	1-4
e. Storage	1-4
f. Reservoir Surface	1-4
g. Dam	1-4
h. Diversion and Regulating Tunnel	1-5
i. Spillway	1-5
j. Regulating Outlets	1-5

<u>Section</u>	<u>Page</u>
2. ENGINEERING DATA	2-1
2.1 Design	2-1
a. Available Data	2-1
b. Design Features	2-1
c. Design Data	2-1
2.2 Construction	2-1
a. Available Data	2-1
b. Construction Considerations	2-1
2.3 Operation	2-1
2.4 Evaluation	2-1
a. Availability	2-1
b. Adequacy	2-2
c. Validity	2-2
3. VISUAL INSPECTION	3-1
3.1 Findings	3-1
a. General	3-1
b. Dam	3-1
c. Appurtenant Structures	3-2
d. Reservoir Area	3-2
e. Downstream Channel	3-2
3.2 Evaluation	3-3
4. OPERATIONAL AND MAINTENANCE PROCEDURES	4-1
4.1 Operational Procedures	4-1
a. General	4-1
b. Warning System	4-1
4.2 Maintenance Procedures	4-1
a. General	4-1
b. Operating Facilities	4-1
4.3 Evaluation	4-1
5. EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES	5-1
5.1 General	5-1

<u>Section</u>	<u>Page</u>
5.2 Design Data	5-1
5.3 Experience Data	5-1
5.4 Test Flood Analysis	5-1
5.5 Dam Failure Analysis	5-2
6. EVALUATION OF STRUCTURAL STABILITY	6-1
6.1 Visual Observation	6-1
6.2 Design and Construction Data	6-1
6.3 Post-Construction Changes	6-1
6.4 Seismic Stability	6-1
7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES	7-1
7.1 Dam Assessment	7-1
a. Condition	7-1
b. Adequacy of Information	7-1
c. Urgency	7-1
7.2 Recommendations	7-1
7.3 Remedial Measures	7-1
7.4 Alternatives	7-1

APPENDIX

APPENDIX A - VISUAL CHECK LIST WITH COMMENTS	A-1
APPENDIX B - ENGINEERING DATA	B-1
APPENDIX C - DETAIL PHOTOGRAPHS	C-1
APPENDIX D - HYDRAULICS/HYDROLOGIC COMPUTATIONS	D-1
APPENDIX E - INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS	E-1

SECTION 5: EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES

5.1 GENERAL

The project is basically a low surcharge storage-high spillage earth embankment, constructed to impound water for recreational use only.

The tributary watershed consists of 3.70 square miles of relatively undeveloped terrain containing no significant storage other than the Blodgett Dam impoundment which, with a surface area of 14 acres, constitutes less than 1% of the total drainage area. With NGVD elevations ranging from about 650 feet to over 1,200 feet and an average slope of about 5%, the watershed topography is considered borderline between rolling and mountainous.

Blodgett Dam is a zoned earthfill structure equipped with a rock lined overflow spillway. The spillway will pass approximately 265% of the routed Test Flood outflow with the pool at the dam crest.

5.2 DESIGN DATA

Detailed SCS hydrologic/hydraulic design data were available and were utilized as applicable.

5.3 EXPERIENCE DATA

The maximum known flood at the dam site occurred June 30, 1973. Maximum water depth in the spillway was about 3 feet, or seven feet below the dam crest. This flow caused some minor erosion in the lower end of the downstream spillway channel.

5.4 TEST FLOOD ANALYSIS

The "Recommended Guidelines for Safety Inspection of Dams" presents a test flood range for significant hazard small size dams of the 100 year frequency to one-half the Probable Maximum Flood (PMF). Selection of the test flood to be utilized in the analysis of a particular dam is dependent upon the proximity of the dam to the upper or lower limits of its size category and upon the perceived risk of future failure. Due primarily to the former consideration, the test flood selected is equivalent to the 100 year frequency flood. The magnitude of this flood was estimated utilizing Weather Bureau projections of the ratio of the 100 year frequency precipitation to the probable maximum precipitation as presented in U.S. Department of Commerce T.P. #40 and applying that ratio to the PMF. The tributary watershed consists of 3.70 square miles of moderately steep, essentially undeveloped terrain about 20% open and 80% wooded. Using a point midway between the curves for "rolling" and "mountainous" watersheds contained in the "Preliminary Guidance for Estimating Maximum Probable Discharge", dated March, 1978, peak inflow to Blodgett Dam impoundment is 1600 cfs. Routed Test Flood outflow, with the pool initially at normal level (el. 644 NGVD) is 1470 cfs with the spillway overtopped 4.2 feet, or 6.8 feet below top of dam. Based upon hydraulics computations, the capacity of the spillway is 8950 cfs, which is approximately 609% of the routed Test Flood outflow at the top of the dam.

SECTION 4: OPERATIONAL AND MAINTENANCE PROCEDURES

4.1 OPERATIONAL PROCEDURES

- a. General - No formal operating procedure exists.
- b. Warning System - No warning system exists.

4.2 MAINTENANCE PROCEDURES

- a. General - The dam receives no regular maintenance. The crushed stone camp road crossing the spillway channel usually requires repair following the spring runoff.
- b. Operating Facilities - The low level outlet gate is reported in good condition. No plan for the periodic maintenance of operating facilities is known to exist.

4.3 EVALUATION

The operation and maintenance procedures at this dam are inadequate to ensure that all problems encountered can be remedied within a reasonable period of time. The owner should establish a written operation and maintenance procedure as well as a warning system to follow in the event of an emergency at the dam.

3.2 EVALUATION

On the basis of the results of the visual inspection, Blodgett Pond Dam is judged to be in fair condition.

If the small trees on the upstream and downstream slopes are allowed to continue to grow, the resulting root systems could create seepage paths which could lead to internal erosion of the dam.

The outlet channel contains dense brush and fallen trees which could restrict the flow of water discharged from the outlet pipes.

The seepage areas observed beneath the outlet pipe are most likely not due to seepage through the embankment but a spring in the abutment. Seepage at the foundation drain is most likely exiting the toe drain shown in the drawings. The bedrock beneath the dam, as observed just downstream of the embankment, is horizontally jointed, and the joints are the most probable cause of the seepage viewed below the dam.

The eroded concrete spillway crest could incur further damage if not repaired.

c. Appurtenant Structures

Spillways

The primary and secondary spillways both occupy the same location at the left end of the dam. The primary spillway is established by a 15 foot by 1 foot notch formed in the concrete sill which forms the spillway crest. This concrete crest is eroded near its centerline as shown in Photo 1. Bedrock is exposed to the left of the spillway crest, also shown in Photo 1.

Outlet Structure

An 18" diameter low level outlet pipe passes through the dam and exits at the downstream toe of the dam at the contact with the right abutment as seen in Photo 6. The low level outlet is controlled by a slide gate housed in a steel well assembly on the upstream dam face as shown in Photo 12. The low level outlet appears in good condition and is reported operable.

d. Reservoir Area - There are no indications of instability along the banks of the reservoir in the vicinity of the dam.

e. Downstream Channel - There are two downstream channels, one downstream from the spillway and the other downstream from the pond drain and foundation drain outlets. The two downstream channels are referred to as the spillway channel and the outlet channel, respectively, in the following sections. The two channels join about 500 feet downstream of the dam.

The outlet channel contains dense brush and fallen trees, as shown in Photo 13. Trees were observed overhanging the channel.

The spillway channel is shown in Photo 14. The floor of the channel is covered with pieces of blasted bedrock and boulders and tall grass. A crushed-stone covered roadway crosses the channel about 250 feet downstream from the spillway crest. As shown in Photo 15 downstream from the roadway the floor of the spillway channel is covered with pieces of blasted bedrock, as shown in Photo 16. Erosion of the side of the spillway channel downstream from the roadway crossing is shown in Photo 17.

Further downstream, the natural brook channel is steep and the banks are wooded with heavy softwood growth. About 500 feet from the dam, the channel banks have been partially cleared of underbrush and there is a boys camp with the lowest structure about 15 feet above the brook channel. The next 2900 feet of brook channel between the boys camp and U.S. Route 5 is steep with undeveloped and wooded banks except in the vicinity of the road where there are four buildings, the lowest of which is about 19 feet above the stream. About 50 feet downstream of the highway bridge is a Boston and Maine railroad Bridge. As shown in Photo 18, this bridge backwall has a marker denoting the height of the November 4, 1927 flood.

SECTION 3 - VISUAL INSPECTION

3.1 FINDINGS

a. General - At the time of inspection on August 5, 1980, the water level in the pond, impounded by the dam, was equal to the crest of the primary spillway with flow over the eroded center as shown in Photo 1. The weather was hot and humid. The general condition of this dam is fair.

b. Dam - The dam is an earth embankment with approximately 2.5H:1V downstream and 3H:1V upstream slopes. The dam consists of two sections separated by a knob of natural ground which is located between about Sta 5+00 and Sta 6+10. (The referenced station numbers were obtained from SCS Drawing No. 3 - "Blodgett Pond, Plan of Damsite," dated June, 1965.) The right section of the dam extends from about Sta 1+00 to Sta 5+00 and the left section is located between about Sta 6+10 and Sta 7+00. The top of the knob of natural ground has been removed down to the elevation of the dam crest.

An operating primary-secondary spillway is located to the left of the dam. A 10" thick, 25' long sill extension shown in Photo 2 forms the right abutment of the spillway with the left section of the dam. On the upstream slope of the right section of the dam is a gate structure which contains the controls for the pond drain. A 6 inch diameter outlet pipe from the foundation drainage system exits at the downstream toe of the right section of the dam about 10 feet left of the pond drain. The upstream slope of the dam is covered with tall grass, brush and some small trees as shown in Photo 3. No riprap was observed on the upstream slope above the waterline. Minor erosion has occurred on the upstream slope at the reservoir elevation as shown in Photo 3.

The crest of the dam is generally about 15 feet wide and has an unpaved roadway as shown in Photo 4. The crest is wider, on the downstream side, at the location of the natural knob. As shown in Photo 5, the downstream slope is covered with tall grass and brush and scattered small pine trees. Water was observed seeping from beneath the 18 inch diameter outlet pipe which exits at the downstream toe of the dam adjacent to the right abutment, seen in Photo 6. Clear seepage was observed downstream of the 6 inch diameter outlet pipe from the foundation drainage system as shown in Photo 7; a rust-colored pool of water, shown in Photo 8, was observed downstream from this seepage area. The SCS drawings for the Blodgett Dam indicate that a rock fill toe drain and blanket drain are located in the downstream toe of the dam at the location of the two seepage areas. The rock toe could not be discerned in the field.

Rust-colored seepage areas were also observed in the natural ground downstream of the downstream toe of the right section of the dam between the location of the 6 inch diameter outlet pipe and the natural knob as shown in Photo 9. The seepage areas are located about 125 feet downstream from the centerline of the crest of the dam. Photo 10, taken approximately 10 feet up the slope from the seepage area shown in Photo 9, shows seepage exiting the original ground at the base of a 10 inch diameter Birch. Another 10 feet up the slope, near the toe of the dam, evidence of animal burrows was noted as shown in Photo 11.

b. Adequacy - Detailed SCS hydrologic/hydraulic design data were available and with field measurements were utilized in conjunction with New England Division - Army Corps of Engineers "Preliminary Guidance for Estimating Maximum Probable Discharges" to perform the computations of outflow capacity.

The detailed engineering data required to perform an in-depth stability analysis of the dam was not available. The final assessment of the dam, therefore, must be based primarily on visual inspection, performance history, and spillway capacity computations.

c. Validity - A comparison of records, data, and visual observations reveals no significant discrepancies, other than those noted above, between design and as-built dimensions.

SECTION 2: ENGINEERING DATA

2.1 DESIGN

a. Available Data - Available data consists of six sheets by the Soil Conservation Service; Sheet 3 of 10 "Plan of Dam Site" June, 1965; Sheets 4 and 5 of 10 "Profiles" June, 1965, Sheet 6 of 10 "Drainage Details" June, 1965; Sheet 7 of 10 "Structural Details" June, 1965 and an unnumbered sheet "Construction Revision - Spillway" August, 1965. Also available was sheet 30 of a series of topographic maps prepared in 1957 at a scale of 1"=200' with a 5 foot contour interval.

b. Design Features - The drawings, computations and inspection reports indicate the design features stated in Section 1.

c. Design Data - Design data consists of information on the drawings as listed in "Available Data" and nine pages of design computations by the Soil Conservation Service prepared during late 1964 and early 1965.

2.2 CONSTRUCTION

a. Available Data - Information as contained in any plans, drawings, or specifications previously listed in "Design Data" or Appendix B.

b. Construction Considerations - Minor variations were noted in the dam as built compared to the design drawings. Sheet 3 indicates that a knoll or knob of natural ground would have projected above the crest of the dam for about 100 feet on the left center of the dam. The projection was removed and the typical dam cross section applies full length.

The concrete capped control section in the spillway was moved about 100 feet upstream in the spillway as shown in the Construction Revision plan of August, 1965.

The access road for the Challenge Wilderness Camp goes along the crest of the dam, turns right along the top of the training wall, runs down the side of the wall and across the spillway channel and continues on down to the camping area in the ravine below the dam.

2.3 OPERATION

Pond level readings are not taken on any regular schedule. No formal operation procedures are known to exist. The pond has been drained twice since 1965 in an attempt to eliminate trash fish which were competing with trout.

2.4 EVALUATION

a. Availability - Existing data was provided by the State of Vermont Agency of Environmental Conservation.

4.	Top Width:	14 ft
5.	Side Slopes:	3H to IV Upstream 2½H to IV Downstream
6.	Zoning:	2 Zones & drain
7.	Impervious Core:	to el. 645±
8.	Cutoff:	Trench
9.	Grout Curtain:	N/A
10.	Other:	N/A
h.	<u>Diversion and Regulating Tunnel</u>	N/A
i.	<u>Spillway</u>	
1.	Type:	Overflow
2.	Length of weir:	15 ft primary 65 ft secondary
3.	Crest el.	primary 644± secondary 645±
4.	Gates:	N/A
5.	Upstream channel:	N/A
6.	Downstream channel:	Rocklined channel
7.	General:	N/A
j.	<u>Regulating Outlets</u>	
1.	Invert:	630.75±
2.	Size:	18 inch diameter
3.	Description:	Corrugated Metal Pipe pond drain
4.	Control mechanism:	Slide gate
5.	Other:	N/A

- | | | |
|----|-------------------------------------|----------------------|
| 5. | Full flood control pool: | N/A |
| 6. | Spillway crest (Ungated): | 644 ₊ |
| 7. | Design surcharge (original design): | 651.2 ₊ |
| 8. | Top of dam: | 655 ₊ |
| 9. | Test flood surcharge: | 648.2 ₊ |
| d. | <u>Reservoir</u> | |
| 1. | Length of normal pool: | 1100 ₊ ft |
| 2. | Length of flood control pool: | N/A |
| 3. | Length of spillway crest pool: | 1100 ₊ ft |
| 4. | Length of pool at top of dam: | 1100 ₊ ft |
| 5. | Length of test flood pool: | 1100 ₊ ft |
| e. | <u>Storage</u> | |
| 1. | Normal pool: | 100 acre-ft |
| 2. | Flood control pool: | N/A |
| 3. | Spillway crest pool: | 100 acre-ft |
| 4. | Top of dam: | 300 acre-ft |
| 5. | Test flood pool: | 160 acre-ft |
| f. | <u>Reservoir Surface</u> | |
| 1. | Normal pool: | 14 acres |
| 2. | Flood control pool: | N/A |
| 3. | Spillway crest: | 14 acres |
| 4. | Test flood pool: | 17 acres |
| 5. | Top of dam: | 21 acres |
| g. | <u>Dam</u> | |
| 1. | Type: | Zoned earthfill |
| 2. | Length: | 714 ₊ ft |
| 3. | Height: | 29 ₊ ft |

i. Normal Operational Procedures - The gated low level outlet is reported operable and remains closed under normal operating conditions. There are no regular operational procedures other than occasional checking.

1.3 PERTINENT DATA

a. Drainage Area - 3.70 square miles of moderately steep, relatively undeveloped terrain which is 20% open and 80% wooded.

b. Discharge at Dam Site - Discharge is from over the primary and secondary spillways. Elevations are in feet referenced to NGVD datum.

1. Outlet Works (conduits):

18" low level pond drain w/water at dam crest el. 655 (normally closed)	60 cfs
--	--------

2. Maximum known flood at dam site:

June 30, 1973. Magnitude estimated from data provided by owner:	750+ cfs
---	----------

3. Ungated spillway capacity at top of dam el. 655 :	8950 cfs
---	----------

4. Ungated spillway capacity at test flood el. 648.2:	1470 cfs
--	----------

5. Gated spillway capacity at normal pool el. 644 :	N/A
--	-----

6. Gated spillway capacity at test flood el. 648.2:	N/A
--	-----

7. Total spillway capacity at test flood el. 648.2:	1470 cfs
--	----------

8. Total project discharge at top of dam el. 655 :	9010 cfs
---	----------

9. Total project discharge at test flood el. 648.2:	1530 cfs
--	----------

c. Elevation (Feet, NGVD)

1. Streambed at toe of dam:	626+
-----------------------------	------

2. Bottom of cutoff:	Unknown
----------------------	---------

3. Maximum tailwater:	633+
-----------------------	------

4. Recreation pool:	644+
---------------------	------

The remainder of the crest wall is 1 foot higher. The spillway outflow channel is founded in bedrock with the left side a cut section, and the right side an earthen training wall. Both are protected with riprap.

To the immediate right of the spillway, a 100 foot section of natural earth, supplemented by cutoff trenches and a drainage system, is incorporated into and forms the left abutment of the main dam.

A gated 18 inch pond drain, with upstream invert at approximately 630.75, penetrates the main embankment at its approximate center.

Elevations are in feet referenced to NGVD datum.

No instrumentation exists at this dam.

c. Size Classification - SMALL - The dam impounds 300 acre-feet of water with the water at the top of the dam, which at elevation 655 is approximately 29 feet above the streambed elevation. Since the storage is between 50 and 1000 acre-feet and the height is between 25 and 40 feet, the dam is in the small category on the basis of both parameters and is thus classified as small in size according to the Recommended Guidelines.

d. Hazard Classification - SIGNIFICANT - If the dam were to be breached, there is potential for considerable downstream damage and the loss of a few lives. Approximately 500 feet downstream from the dam is a boys summer camp with lean-to type buildings about 15 feet above the streambed. The rapid 5 foot rise in stage from 7 to 12 feet would likely not damage the structures but could, under certain circumstances, catch personnel at lower elevations. Further downstream, about 3400 feet from the dam, U.S. Route 5 crosses about 16 feet above the streambed. The sudden 10 foot rise in stage here from 9 feet to 19 feet would inundate and probably destroy this bridge. About 3550 feet downstream from the dam the failure wave would overtop the Boston and Maine Railroad bridge by approximately 2 feet and damage or destroy it.

e. Ownership - Mr. Putnam W. Blodgett
Challenge Wilderness Camp
Bradford, Vermont 05033
(802) 649-1363

f. Operator - As above.

g. Purpose of Dam - Recreation.

h. Design and Construction History - The following information is believed to be accurate based upon plans and correspondence available and from conversations with the dam owner. The dam was designed in 1965 by the U.S. Department of Agriculture, Soil Conservation Service, and constructed by the owner during that same year. Except for some minor erosion repairs on the spillway outlet channel, there have been no post-construction changes.

PHASE I INSPECTION REPORT

BLODGETT DAM

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

a. Authority - Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. James W. Sewall Company has been retained by the New England Division to inspect and report on selected dams in the State of Vermont. Authorization and notice to proceed were issued to James W. Sewall Company under a letter of April 2, 1980 from William E. Hodgson, Jr. Colonel, Corps of Engineers. Contract No. DACW 33-80-C-0051 has been assigned by the Corps of Engineers for this work.

b. Purpose of Inspection Program - The purposes of the program are to:

1. Perform technical inspection and evaluation of non-federal dams to identify conditions requiring correction in a timely manner by non-federal interests.
2. Encourage and prepare the States to quickly initiate effective dam inspection programs for non-federal dams.
3. To update, verify and complete the National Inventory of Dams.


1.2 DESCRIPTION OF PROJECT

a. Location - The dam is located on the course of Roaring Brook about 3,700 feet upstream of its confluence with the Connecticut River, in the Town of Bradford, County of Orange, State of Vermont. The dam is shown on the Newbury, N.H.-Vt. 7.5 minute Quadrangle Map having coordinates N44° 01.7' and longitude W 72° 06.1'.

b. Description of Dam and Appurtenances - The dam, initially constructed in 1965, consists of a zoned earthfill embankment having a total length of approximately 714 feet, including an overflow spillway founded in bedrock, located to the left of the dam.

The embankment has a top elevation of approximately 655, is 29 feet in height above the streambed and is 14 feet wide at the crest. The upstream slope is inclined at 3 horizontal to 1 vertical; the downstream slope is inclined at 2½ horizontal to 1 vertical and is equipped with a drainage system.

The primary spillway has a crest elevation of about 644 and is 15 feet long formed in the 80 foot long concrete crest wall of the rock spillway section.



Gravel
Pits

Rogers Hill
Cem

Radio
Tower

29

TRAIL

South Newbury

Brook

Sandpit

Roaring

Sandpit

1069

85

BLODGETT DAM

B R A D F O R D

Brook

BM
410

CONNECTICUT

Sawyers
Ledge

BM
406

Cem
Oxbow
High Sch

Sawyer
Cem

Bradford

Bradford

USGS QUADRANGLE
NEWBURY, N.H. - VT. 1973
EAST CORINTH, VT. 1973

River Road
Cem

0 1/2 MILE



OVERVIEW PHOTO

U.S. ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

JAMES W. SEWALL COMPANY
CONSULTANTS
OLD TOWN, MAINE

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

Blodgett Dam - VT 00117

Bradford, Vermont

August 5, 1980

5.5 DAM FAILURE ANALYSIS

Utilizing the April, 1978, "Rule of Thumb Guidance for Estimating Downstream Dam Failure Hydrographs", the peak failure outflow would be 33,600 cfs with the pool initially at the top of the dam (655± NGVD). A breach of the dam would result in a rise of 5 feet in the water level of the stream at the initial impact area, a boys camp 500 feet downstream from the dam. This 5 foot rise in flood stage corresponds to an increase in flow of 24,650 cfs and an increase in the water level from a depth of 7 feet just before the breach, to a depth of 12 feet just after the breach. The rapid 5 foot increase in the water level would not likely damage the structures, the lowest of which is about 15 feet above the brook channel, but could potentially catch personnel unaware at lower elevations in the camping area. Further downstream, about 3400 feet from the dam, U. S. Route 5 crosses about 16 feet above the stream bed. The sudden 10 foot rise in stage here from 9 feet to 19 feet would inundate and probably destroy this bridge. About 3550 feet downstream from the dam the failure wave would overtop the Boston and Maine Railroad bridge by approximately 2 feet and damage or destroy it. Because of the potential for loss of a few lives in the initial impact area and the considerable downstream damage which would ensue from a breach, Blodgett Dam is classified as a "Significant Hazard" dam.

SECTION 6: EVALUATION OF STRUCTURAL STABILITY

6.1 VISUAL OBSERVATION

The visual inspection did not disclose any immediate stability problems. However, if the small trees on the upstream and downstream slopes continue to grow, the resulting root masses could lead to internal erosion of the dam. The dense brush and fallen trees in the outlet channel could restrict the flow of water discharged from the outlet pipes. The seepage areas observed at the downstream toe of the dam should be monitored. The concrete spillway crest could incur further damage if not repaired.

Erosion observed on the side of the downstream spillway channel is judged too remote from the dam to be of structural consequence.

6.2 DESIGN AND CONSTRUCTION DATA

The available data on the existing plans for the dam are inadequate for analyzing the stability of the dam.

6.3 POST-CONSTRUCTION CHANGES

There is no record of post-construction changes.

6.4 SEISMIC STABILITY

The dam is located in Seismic Zone 2, and in accordance with the recommended Phase I guidelines does not warrant seismic investigation.

SECTION 7: ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

7.1 DAM ASSESSMENT

- a. Condition - Based upon the visual inspection, the dam is judged to be in fair condition.
- b. Adequacy of Information - Due to the lack of adequate design and construction data for this dam, the assessment of safety is based solely on the visual inspection.
- c. Urgency - The remedial measures and recommendations presented below should be implemented by the owner within 1 year after receipt of this Phase I Inspection Report.

7.2 RECOMMENDATIONS

The owner should retain a qualified registered engineer to design a seepage collection system that would permit measurement of the seepage observed at the downstream toe of the embankment and to supervise removal of trees and root systems as noted below and the backfilling of areas thus excavated with suitable material.

7.3 REMEDIAL MEASURES

- a. The tall grass and brush growing on the dam slopes should be mowed and subsequent new growth cut regularly. The trees and bushes growing on the slopes and to a distance of 25 feet downstream should be removed and later new growth cut every two years.
- b. The brush and fallen trees in the outlet channel should be removed. Trees overhanging the channel should also be removed.
- c. The eroded concrete spillway crest should be repaired.
- d. A formal annual inspection program by qualified engineers, with repairs as necessary, should be established by the owner.
- e. A formal downstream warning system, to be implemented in the event of flood flow or imminent dam failure conditions, should be developed by the owner.
- f. A formal program of operating and maintenance procedures, including exercising of the drain valve, should be instituted and fully documented to provide accurate records for future reference.

7.4 ALTERNATIVES

This study has identified no practical alternative to the above recommendations.

APPENDIX A
VISUAL CHECK LIST WITH COMMENTS

VISUAL INSPECTION CHECKLIST PARTY ORGANIZATION

PROJECT El Estero de San Juan

DATE Aug. 5, 1970

TIME 9:30 AM

WEATHER Cloudy

W.S. ELEV. U.S. DN.S.

PARTY:

- | | |
|--|---------------------|
| 1. <u>Mr. J. L. Thompson</u> <u>S.D.M.</u> | 6. <u> </u> |
| 2. <u>Mr. J. L. Thompson</u> <u>S.D.M.</u> | 7. <u> </u> |
| 3. <u>Mr. J. L. Thompson</u> <u>S.D.M.</u> | 8. <u> </u> |
| 4. <u>Mr. J. L. Thompson</u> <u>S.D.M.</u> | 9. <u> </u> |
| 5. <u>Mr. J. L. Thompson</u> <u>S.D.M.</u> | 10. <u> </u> |

PROJECT FEATURE

INSPECTED BY

REMARKS

- | | |
|--|---|
| 1. <u>Dam Encasement</u> | <u>D.P.L. S.L.M. S.D.M. R.L.H. C.A.H.</u> |
| 2. <u>Outlet Channel</u> | <u>D.P.L. S.L.M. S.D.M. R.L.H. C.A.H.</u> |
| 3. <u>Setback, 1/2 mile from Discharge</u> | <u>D.P.L. S.L.M. S.D.M. R.L.H. C.A.H.</u> |
| 4. <u> </u> | <u> </u> |
| 5. <u> </u> | <u> </u> |
| 6. <u> </u> | <u> </u> |
| 7. <u> </u> | <u> </u> |
| 8. <u> </u> | <u> </u> |
| 9. <u> </u> | <u> </u> |
| 10. <u> </u> | <u> </u> |

2

PROJECT Albion Dam DATE 10/1/77

PROJECT FEATURE Dam Embankment NAME John J. ...

DISCIPLINE Structural Engineering NAME ...

Geotechnical Engineering

AREA EVALUATED	CONDITION
<u>DAM EMBANKMENT</u>	
Crest Elevation	655 MGD
Current Pool Elevation	644 MGD
Maximum Impoundment to Date	N.A.
Surface Cracks	None observed
Pavement Condition	No pavement on crest
Movement or Settlement of Crest	None observed
Lateral Movement	None observed
Vertical Alignment	No misalignment observed
Horizontal Alignment	No misalignment observed
Condition at Abutment and at Concrete Structures	Some seepage observed along junction of downstream slope and right abutment.
Indications of Movement of Structural Items on Slopes	None observed
Trespassing on Slopes	Crest is unimproved roadway used for vehicular traffic.
Sloughing or Erosion of Slopes or Abutments	Minor erosion on upstream slope at present water level.
Rock Slope Protection - Riprap Failures	No riprap observed on upstream slope
Unusual Movement or Cracking at or Near Toe	None observed
Unusual Embankment or Downstream Seepage	Seepage evident from 6 in. outlet pipe and from native ground downstream of downstream toe.
Piping or Boils	None observed
Foundation Drainage Features	Outlet pipe from downstream toe drain observed
Toe Drains	None observed
Instrumentation System	None observed
Vegetation	Dense brush to small trees on downstream slope.

PERIODIC INSPECTION CHECKLIST

PROJECT _____ DATE _____
 PROJECT FEATURE _____ NAME _____
 DISCIPLINE _____ NAME _____

AREA EVALUATED	CONDITION
<u>DIKE EMBANKMENT</u> Crest Elevation Current Pool Elevation Maximum Impoundment to Date Surface Cracks Pavement Condition Movement or Settlement of Crest Lateral Movement Vertical Alignment Horizontal Alignment Condition at Abutment and at Concrete Structures Indications of Movement of Structural Items on Slopes Trespassing on Slopes Sloughing or Erosion of Slopes or Abutments Rock Slope Protection - Riprap Failures Unusual Movement or Cracking at or Near Toes Unusual Embankment or Downstream Seepage Piping or Boils Foundation Drainage Features Toe Drains Instrumentation System Vegetation	<i>There is no dike on this project</i>

PROJECT Bay AreaDATE April 5 1993PROJECT FEATURE _____NAME SDMDISCIPLINE _____NAME _____

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u></p> <p>a. Approach Channel</p> <p> Slope Conditions</p> <p> Bottom Conditions</p> <p> Rock Slides or Falls</p> <p> Log Boom</p> <p> Debris</p> <p> Condition of Concrete Lining</p> <p> Drains or Weep Holes</p> <p>b. Intake Structure</p> <p> Condition of Concrete</p> <p> Stop Logs and Slots</p>	<p><i>No outlet - under water</i></p>


DATE 11-1-59

NAME _____

NAME _____

A-5

PROJECT _____ DATE _____
PROJECT FEATURE _____ NAME _____
DISCIPLINE _____ NAME _____
Geotechnical Inspection *10-10-10*

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - TRANSITION AND CONDUIT</u> General Condition of Concrete Rust or Staining on Concrete Spalling Erosion or Cavitation Cracking Alignment of Monoliths Alignment of Joints Numbering of Monoliths	

PROJECT _____

DATE Oct 17 1997

PROJECT FEATURE _____

NAME SEVEN

DISCIPLINE _____

NAME SEVEN

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL</u></p> <p>General Condition of Concrete</p> <p>Rust or Staining</p> <p>Spalling</p> <p>Erosion or Cavitation</p> <p>Visible Reinforcing</p> <p>Any Seepage or Efflorescence</p> <p>Condition at Joints</p> <p>Drain holes</p> <p>Channel</p> <p>Loose Rock or Trees Overhanging Channel</p> <p>Condition of Discharge Channel</p>	<p><i>None observed</i></p> <p><i>Some trees overhanging channel</i></p> <p><i>Brush growing in channel, cobble and boulders in channel.</i></p>

PERIODIC INSPECTION CHECKLIST

PROJECT Spillway Weir

DATE August 17, 1960

PROJECT FEATURE Spillway Weir


NAME Edw. J. ...

DISCIPLINE Structural Engineering

NAME ...

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u>	
a. Approach Channel	
General Condition	Good
Loose Rock Overhanging Channel	None observed
Trees Overhanging Channel	None observed
Floor of Approach Channel	Goodie covered
b. Weir and Training Walls	
General Condition of Concrete	The spillway crest is formed by a concrete cap on existing ledge.
Rust or Staining	This concrete is eroded near its centerline
Spalling	
Any Visible Reinforcing	No
Any Seepage or Efflorescence	None observed
Drain Holes	None observed
c. Discharge Channel	
General Condition	Good
Loose Rock Overhanging Channel	None observed
Trees Overhanging Channel	Some trees overhanging channel.
Floor of Channel	Covered with goodie and pieces of blasted rock.
Other Obstructions	Crushed stone covered roadway crosses spillway channel about 250' downstream of spillway crest.

PROJECT _____ DATE _____
 PROJECT FEATURE _____ NAME _____
 DISCIPLINE _____ NAME _____
 Section 101.00 - Bridge Inspection D. 9.1. 8.1.1.1

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - SERVICE BRIDGE</u></p> <p>a. Super Structure</p> <ul style="list-style-type: none"> Bearings Anchor Bolts Bridge Seat Longitudinal Members Underside of Deck Secondary Bracing Deck Drainage System Railings Expansion Joints Paint <p>b. Abutment & Piers</p> <ul style="list-style-type: none"> General Condition of Concrete Alignment of Abutment Approach to Bridge Condition of Seat & Backwall 	<p><i>There is no service bridge</i></p> 

APPENDIX B
ENGINEERING DATA

VI. General Comments

Dam is in overall good condition but shows lack of maintenance. Drainage system and seepage should be further investigated.

Report By

A. Peter Berencart

Date 10-23-79

A. Peter Berencart, PE
Dam Safety Engineer

Attachments:

- ① Photos when developed
- ② Copy of SCS plans (1965) showing general area of seepage.

Note: The writer did not have this plan with him during the inspection so notations are approximate.

my to Dick Gallo SCS 10/25/79 a.m.

2. Other Gates, Drains, Appurtenances Access pipe 51"x34"
vertical riser on ups WL had covered on. Did not inspect
~~condition~~ Possibly some ^{infiltration} leakage into pond drain
because of rust color water sediments(?)
3. Remarks _____

IV. Operation and Maintenance

Apparently no brush has been cut since last inspected
(10/4/76).

V. Inspection Summary

A. Information Obtained

1. Photographs ☒
2. Dimensions _____
3. Other _____

B. Additional Information Needed

Investigate French drain & seepage.

C. Overall Condition of Dam

Good but needs maintenance.

10. Stop Logs, Flash Boards None

11. Remarks OK. but vegetation may become a problem if left too long.

B. Emergency Spillway

Type see "A" above

Controlled or Uncontrolled _____

1. Approach Channel _____

2. Transition _____

3. Control Section _____

4. Discharge Channel _____

5. Remarks _____

C. Drawdown Facilities, Gates, Drains, Appurtenances, Etc.

1. Drawdown Facility 18" pond drain

Condition Outlet, only, visible. Seepage (rust colored) exiting end of pipe. Some sediments (?) - rust colored. Flowing water (5-10 gpm) exiting from stone fill under pipe from general area of blanket drain.

10. Alignment OK

11. Remarks Good condition

III. Condition of Outlet Works

A. Principal Spillway and Emergency Spillway (Combined)

Type Earth, rock cut, concrete control section, training
dike right side

Controlled or Uncontrolled uncontrolled

1. Approach Channel clear

2. Transition clear

3. Control Section clear

4. Discharge Channel Tall grass + brush ^{& pine trees} along right side
clear of debris.

5. Intake Structure N/A

6. Conduit N/A

7. Outlet Structure N/A

8. Trash Racks N/A

9. Anti-vortex Devices N/A

14. Alignment OK
15. Movement none apparent
16. Remarks Embankment stable but brush growing up.
Apparently drainage system (trough drain) is plugged and
seepage is being forced out at along toe of old ground
near old track bed.

C. Crest

1. Vegetative Cover grass cover - OK except in wheel
tracks
2. Erosion none significant
3. Evidence of Overtopping none
4. Settlement, Cracks none observed
5. Animal Burrows none observed
6. Debris none
7. Use of crest (road, trail, etc.) Crest provides vehicular
access - no grass in wheel tracks
8. Structural OK
9. Abutments OK

B. Downstream Face or Slope and Toe

1. Vegetative Cover Grass cover being taken over by brush.
A few small pines.
2. Erosion none observed
3. Slumps, Slides, Cracks none observed
4. Animal Burrows a few ~ rat size
5. Slope Protection vegetated
6. Debris none
7. Seepage (Flowing water - rust colored)
Significant all along toe of slope (old ground) between
stations 3+0 → 5+0. Seepage has pooled in low area and standing in
old brook bed. No active seepage on embankment but "wet type" vegetation
observed 1/3-1/2 way up slope in same area.
8. Piping Possible along active toe (old ground) and possibly some
near toe of embankment near pond drain and fore drain.
9. Boils None apparent.
10. Toe Drains 6" C.G.M.P. to left of 18" pond drain was dry but
seepage existing below and around it.
11. Scour none
12. Structural slope is firm, appears stable
13. Abutments right contact damp

II. Condition of Main Structure

Type of Construction Zoned E/F

A. Upstream Face or Slope

1. Vegetative Cover Grass cover being taken over by brush and small (3-8') evergreens (mostly white pine)
2. Erosion none observed
3. Slumps, Slides, Cracks none observed
4. Animal Burrows none observed
5. Slope Protection vegetated
6. Debris none
7. Structural stable
8. Abutments OK
9. Alignment OK
10. Movement none apparent
11. Remarks Good condition except for brush & trees.

State of Vermont
Agency of Environmental Conservation
Department of Water Resources
Montpelier, VT 05602

DAM INSPECTION REPORT

Name BLODGETT DWR No. 24-2
Town Bradford NDS No. VT00 117
Owner Potnam W. Blodgett Inspection Date 10-22-79
Address Bradford, Vt. 05033 Last Inspected 10-4-76
Telephone _____ Hazard Class 3 check (scs 2')
Size Category III

PERSONS PRESENT AT INSPECTION (Name and Organization):

Inspecting Party A. P. Barranco, Jr. - Dept of Water Resources

Others _____

I. General Conditions at Time of Inspection

Weather Clear, hot (80°+) Ground Conditions Dry

Water Surface Elevation -0.05' Datum low flow section (conc.)

Accessibility fully accessible

Reservoir Area clear

Remarks Stopped at Blodgett house and spoke with Mr. Blodgett's mother. Got permission to inspect dam.

GENERAL		
TO	NOTED	DATE
DJM	Ljm	11/24/76
DHS	QHS	11-24-76
ASR		

MANAGEMENT & ENGINEERING DIVISION

802/828-2393

November 23, 1976

Mr. Putnam W. Blodgett
Bradford, VT 05033

Subject: Blodgett Dam - Bradford

Dear Mr. Blodgett:

Thank you for allowing engineers of this Division to make a visual inspection of your dam, and for visiting our office on October 18 concerning their findings.

As you are aware, no signs of stress or deterioration were found during the inspection. There was no seepage noted except at the toe drains. Overall, the embankment seemed to be in stable condition and structurally sound. The spillway was also found to be in good condition and apparently functioning well.

It was noted though, some maintenance is needed. This is generally limited to brush and tree cutting on the dam and mowing the grass cover. Similar work is needed in the spillway area. We generally encourage this activity to maintain the protective plant cover. Mowing prevents the growth of woody plants and helps develop a cover and root system more resistant to runoff.

If we may be of further assistance, or should you have additional questions, please feel free to contact Donald H. Spies, Dam Construction Engineer, at this office.

Sincerely yours,

Andre J. Rouleau
Assistant Director

DJM/v1

VERMONT DEPARTMENT OF WATER RESOURCES
INFORMATION SHEET

Name of Dam Blodgett Town Bradford
Owner Putnam Blodgett Name of Stream Rearing Brook
Address Bradford Vermont Classification TII ?
05033

U.S.G.S. Coordinates: Lat. 44° 01' 40" Long. 72° - 6' 5"

U.S.G.S. Map Woodsville N.H. Aerial Photos VT-62-H 43 103 to 106

U.S.G.S. Elev. @ Spillway _____

Total Length of Dam 585 ft Crest Width of Emergency 5.5 ft
Spillway

Width of Top 14 ft. Maximum Height 22.4 ft

Spillway Capacity: Principal 43 cfs * Emergency 4165 cfs @ DHW.
12.0 ft @ DHW

Pond Area 14.4 A @ NWL Drainage Area 4.85 S. M.

Pond Volume: Normal Water Level 28.6 AF Design High Water Level 218.5 AF

Maximum Water Depth: Normal Water Level 17 ft Design High Water 24.2 ft
Level

Storage Before Emergency Spillway is Used 14.4 AF

Use of Reservoir Recreation

Description of Dam: Zoned earth fill with 3 on 1 upstream
slope and 2 1/2 on 1 downstream slope.

Description of Spillway(s): P.S. - 1 ft notch 15 ft wide in C.S.
C.S. - Concrete weir with 1/2 ft notch and channel 17 ft
wide sloping 1:1

Designed by SCS Year Built 1965

Hearing Date June 25, 1965 Order Date August 24, 1965

Additional Remarks: 1 ft depth of water in C 285 cfs
2.85 1027

SUMMARY OF DATA AND CORRESPONDENCE


<u>DATE</u>	<u>TO</u>	<u>FROM</u>	<u>SUBJECT</u>	<u>PAGE</u>
-	-	-	Vermont Dept. of Water Resources Information Sheet	B-4
10-23-76	Putman Blodgett	Andre J. Rouleau	Inspection Results	B-5
10-4-76	File	A.P. Barranco Dam Safety Eng.	Inspection Report	B-6
1-4-74	Putman Blodgett	John Cerutti	Draining of Pond	B-14
12-26-73	John Cerutti	Putman Blodgett	Draining of Pond	B-15
12-18-75	Putman	John Cerutti	Draining of Pond	B-16
11-4-65	File	Donald Webster	Completion of Dam	B-17
8-17-65	John Cerutti	Kenneth Wilson	Spillway Revision	B-18
'64-'65	File	S.C.S.	Design Sheets	B-19
6 to 8-65	-	S.C.S.	Design plans - reduced to 1/2 size	B-28
1957	-	-	Topographic sheet - Reduced to 1/2 size	B-34

BLODGETT DAM

EXISTING PLANS

On file with the Vermont Department of Water Resources:

1. U. S. Department of Agriculture
Soil Conservation Service
Blodgett Pond
Bradford, Vermont
Sheet 3 of 10 - Plan of Dam Site, June, 1965
Sheet 4 of 10 - Profiles, June, 1965
Sheet 5 of 10 - Profiles, June, 1965
Sheet 6 of 10 - Drainage Details, June, 1965
Sheet 7 of 10 - Structural Details, June, 1965
Unnumbered Sheet Construction Revision - Spillway August, 1965
2. Vermont Department of Highways
Sheet 30 of a series of topographic maps prepared in 1957 at a
scale of 1"=200' with a 5 foot contour interval. This covers the
site of Blodgett Dam.






U. S. ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WILTHAM, MASSACHUSETTS



NATIONAL PROGRAM OF INSPECTION OF NON-FEDERAL DAMS

BLOODGETT DAM
BRADFORD, VT

NO.	REVISION	DATE	BY	CHK.	APPROVED	SHEET	OF
1							



11/2

FILE COPY

TO	DATE
DEC	1/7/74
ARR	
DNB	
FILE	

MANAGEMENT & ENGINEERING DIVISION

January 4, 1974

Mr. Putnam W. Blodgett
Bradford
Vermont 05033

Dear Mr. Blodgett:

We appreciate your prompt reply to our letter of December 18, 1973, relative to the draining and de-silting of your pond.

We recognize that if the work was carried out as noted, sediment transportation down Roaring Brook was minimized. However, on the basis of the present information, it is our opinion the work was a de-silting operation. In your future operation and maintenance of the dam, we would caution you to refrain from performing this type of work without notifying and seeking approval of the Board as noted in the Order.

We will plan to have our dam construction engineer review your project along with his routine inspections this year.

Very truly yours,

John E. Cerutti, Director
Management & Engineering Division

SEC/DJM/jcd
cc: C. Bothwell, Water Resources Board

Putnam W. Blodgett

CHALLENGE WILDERNESS CAMP / BRADFORD, VERMONT 05033

December 26, 1973

Mr. John E. Cerutti, Director
Management & Engineering Division
Agency of Environmental Conservation
Montpelier, Vermont 05602

TO	NOTED	DATE
SEC -		
AJR	<i>[initials]</i>	1/3/74
DJM	<i>[initials]</i>	1/4/74
DHS	<i>[initials]</i>	1-3-74

Dear Mr. Cerutti:

SPEND TO

This is in reply to your letter of December 18 inquiring about the draining and 'de-siltation' of my pond.

The pond was drained for two reasons: 1) to try to reclaim the pond from the trash fish that were destroying the trout, and 2) to remove part of the delta that had built up at the inlet due to the natural inflow, the construction of I-91 upstream, and this year's June 30 flood.

The SCS dozer pushed the material up on the bank above waterlevel.

As this work took place after the pond had been drained and was out of the streambed and as the pond drain is above the pond bottom no sediment went down Roaring Brook.

Therefore, I did not consider that any 'de-siltation' would or did take place.

Sincerely yours,

Putnam W. Blodgett
Putnam W. Blodgett

FILE COPY

ROUTING		
GENERAL		
TO	NOTED	DATE
DHS	DHS	12-18-73
DGM	DGM	12/18/73
OR	-	12/18
JEC	mc	
SUSPEND TO		
FILE		

MANAGEMENT & ENGINEERING DIVISION

December 18, 1973

Mr. Putnam W. Blodgett
Bradford
Vermont 05033

Dear Mr. Blodgett:

We have been informed you recently drained and de-silted your pond on Roaring Brook in Bradford. We wish to remind you Condition No. 10 of the Order Approving and Authorizing the Construction of a Dam issued August 24, 1965, reads, "There shall be no de-silting, so-called, with respect to the operation and maintenance of said dam except upon the prior written approval of the Board and on such terms and conditions as it shall specify."

We therefore request you please provide an explanation of how and why this occurred.

Sincerely yours,

John E. Cerutti, Director
Management & Engineering Division

JEC/DHS/lmp

cc: Cathy Bothwell, Water Resources Board

OFFICE MEMORANDUM

DATE November 4, 1965

TO: For the Record

FROM: Donald W. Webster

SUBJECT: Blodgett Dam, Bradford

On November 3, 1965, the writer and John E. Cerutti inspected the dam at the Blodgett family camping area on Roaring Brook in the Town of Bradford. The impoundment section on the dam is complete and water has been impounded in the dam to within four feet of design normal water level. The spillway crest (concrete) has been completed, and with the exception of shaping up the spillway outlet channel downstream of the crest, which the contractor was doing on this date, the dam is substantially completed in accordance with plans and specifications on file in this office.

ROUTING		
GENERAL		
TO	NOTED	DATE
DWW	DWW	11-5
JEC	JEC	11-5
RWT	JE	11-5
SUBMITTED TO		
FILE		

UNITED STATES DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

19 Church Street
Burlington, Vermont
August 17, 1965

Mr. John E. Cerutti, Hydraulic Engineer
Department of Water Resources
State Office Building
Montpelier, Vermont

Dear John:

Enclosed you will find plans for proposed spillway revision on the Blodgett RC&D dam.

In the event any part of this does not meet with your approval we would appreciate being advised at your earliest convenience.

The requirements of your department for the compaction of the earth fill in the upper part of the dam have been met. Spillway rock excavation is about complete and I expect concrete work will be started soon.

Very truly yours,



Kenneth P. Wilson
State Conservation Engineer

cc: P. Blodgett
J. Bryant

Enclosure

ROUTING		
GENERAL		
TO	NOTED	DATE
DEC	jrc	8-23
SUSPEND TO		
FILE		

GEOLOGY REPORT
White River RC&D Project
Blodgett Pond,
Bradford, Vermont

Prepared by:

John H. Bryant, Design Engineer
Louis Dondero, Soil Scientist

Date: 12-21-64

A. General

Dates of Exploration: 8/7/64, 9/3/64 - Louis Dondero
John H. Bryant

Location: Town of Bradford, Orange County, Vermont

Structure Class: "b"

Equipment Used: Massey-Ferguson MF 185 Backhoe

Site Data:

Drainage Area: 4.85 sq. miles, 3100 acres
Maximum Pool Depth: 22 feet
Purpose: Recreation
Maximum Height of Dam: 32.5 feet
Top Length of Dam: 345 feet
Emergency Spillway: Vegetated
Principal Spillway: Concrete Weir
Volume of Fill: 16,000 cubic yards

Methods of Exploration:

Backhoe, Hand Auger, Seismic

B. Surface Geology and Physiography

Connecticut River Valley modified by glacio fluvial and glacial lacustrine deposits to an elevation of 600± feet. At elevations above 600± feet the area is mainly glacial till and outcrops of bedrock. The bedrock occurs at lesser elevations in streambeds and deep erosion cuts.

REFERENCE

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
ASSISTING

SOIL AND WATER CONSERVATION DISTRICT

DRAWING NUMBER

SHEET _____ OF _____

DATE _____

STATE NEBRASKA PROJECT BLODGETT POND
BY J.H. DATE 1-10-65 CHECKED BY FMW DATE 2-23-65 JOB NO. _____
SUBJECT CRITERIA & STRUCTURE CLASSIFICATION SHEET _____ OF _____

DESIGN CRITERIA

CLASS 'B' STRUCTURE - S.C.S. E.M. 27

(SCS) PRINCIPAL SPILLWAY STORM - 6 HR - 50 YR (MC II)

(SCS) FREQUENCY OF OPERATION OF EMERGENCY SPILLWAY - 2%

(SCS) EMERGENCY SPILLWAY STORM - 1.25 X MIN. E.W.P. REC.
(MC II)

(SCS) FREEBOARD - 1.25 X MIN. E.W.P. REC.
(MC II)

(U.S. W.R. DEPT) ANTI-SEEP COLLARS - 125% INCREASE FROM TOE TO DRAIN

STRUCTURE CLASSIFICATION COMPUTATIONS

HEIGHT 30.9'

STORAGE 290.5 A.F.

POP. DAMAGE CENTER 0

FLOOD PLAIN WIDTH 150'

DISTANCE TO DAMAGE CENTER 0.35 MI

$H_{ys} = 8.405$

$K_s = 7.3$ $K_p = 1$ $K_w = 7.6$ $K_d = 0.55$

$K = \frac{K_s + K_p + K_w}{K_d} = \frac{7.3 + 7.6 + 1}{0.55} = \frac{15}{0.55} = 27.3$

This recreation dam is located in the Township of Bradford, Vermont.

A summary of pertinent design information is given on sheet 2 of this report.

Criteria and procedures used in this design are given in the following Soil Conservation Service publications:

National Engineering Memorandum No. 27, Limiting Criteria for the Design of Earth Dams

National Engineering Memorandum No. 42, Reinforced Concrete Pipe Drop Inlet Barrels

National Engineering Memorandum No. 50, Drop Inlet Spillway Standards

National Engineering Handbook No. 4A, Hydrology

National Engineering Handbook No. 5, Hydraulics

National Engineering Handbook No. 8, Geology

Engineering Division Technical Release No. 2, Earth Spillways

The results of hydrologic and hydraulic computations are given on sheet 3 of this report.

This structure consists of a compacted earth fill with a cutoff extending down into the foundation. A drainage system is installed to control seepage through the embankment and foundation.

The principal spillway is a weir section located in the emergency spillway.

The emergency spillway is designed as a rock cut in the left abutment.

DESIGN REPORT SUMMARY

I. Watershed data

- | | |
|------------------------------------|-----------|
| A. Structure class | (b) |
| B. Drainage area | 3,100 Ac. |
| C. Time of concentration - T_c | 1.77 Hrs. |
| D. Hydrologic curve number - C_n | |
| 1. Moisture condition II | 64 |
| 2. Moisture condition III | 82 |

II. Principal spillway


- | | |
|--------------------|------------|
| A. Weir size | 1 x 15 Ft. |
| B. Pond drain size | 18 In. |

III. Emergency spillway

- | | |
|---|---------------|
| A. Width | 80 Ft. |
| B. Side slopes | 1-1/2 and 2:1 |
| C. Exit slope | 0.0167 Ft/Ft. |
| D. Maximum velocity at control section (D.H.W.) | 11.1 Ft/Sec. |

IV. Earth fill

- | | |
|---------------|--------------|
| A. Height | 32 Ft. |
| B. Volume | 22,000 C. Y. |
| C. Compaction | Class A |



TYPICAL SECTION OF DAM


U. S. DEPARTMENT OF AGRICULTURE - SOIL CONSERVATION SERVICE

Element of Structure	Determining Factor	Elevation	Surface Area Acres	Storage		Inflow		Peak Outflow c.f.s.
				Acres-Feet	Inches*	Volume Inches*	Rate c.f.s.	
Crest of principal spillway		184.0	14.4	98.7	0.38			
Crest of emergency spillway	50-year frequency storm, 6 hour rainfall moisture condition III	185.0	15.0	113.0	0.44	1.94		
Design high water	1.25X minimum 6 hour precipitation - ES-1020 sheet 2 of 5, moisture condition II	191.2	19.0	218.5	0.85	3.67		
Top of dam	1.25X minimum 6 hour precipitation - ES-1020 sheet 3 of 5 moisture condition II	195.2	21.2	298.5	1.16	8.05		

*Inches of runoff from controlled area of 3100 acres

12-15-48
1-15 PM


200000000
STILL STORAGE CURVE



STORAGE - AKC FEET

1-23-65 JMB
3-65 FMW
BLDGGETT POND


STAGE-AREA CURVE



NOTE CORRECTION FOR
VOLUME OF DATA
INCLUDED

STATE VERMONT PROJECT BUDGET POND
BY JHB DATE 3-24-65 CHECKED BY DATE JOB NO.
SUBJECT CONSTRUCTION AND POND DRAIN CAPACITY SHEET 4-11 OF

$\eta = 0.025$



$$K_0 (\text{ENTRANCE}) = 0.78$$

$$K_2 (\text{ENLARGEMENT}) = 1$$

$$K_{45} (\text{BEND})$$

$$K_{45} = \left[1 - \left(\frac{90-45}{90} \right)^2 \right] K_{90}$$

$$R \approx 5' \quad R/d = \frac{5}{1.5} = 3.34 \quad K_{90} = 0.35 \text{ NEH 5 Pg. 5.5-5}$$

$$K_{45} = [1 - 0.25] 0.35 = 0.25$$

$$K_p (\text{PIPE FRICTION}) = 0.06743$$

$$C_p = \sqrt{\frac{2.3}{1 + K_2 + K_{45} + K_p L + K_0}}$$

$$= \sqrt{\frac{64.4}{1 + 1 + 0.25 + 0.06743 \times 218 + 0.78}}$$

$$= \sqrt{\frac{64.4}{12.73}} = 1.90$$

$$Q = C_p A H^{3/2} = 1.90 \times 177.8^{3/2} = 336.5 \text{ cfs}$$

12-23-64 9413


STATE-STATE COMPUTATIONS

[illegible]

APPENDIX C
DETAIL PHOTOGRAPHS



2025 RELEASE UNDER E.O. 14176

Def 2



P. 32



10/2



RIPRAP
EQUIP A 10' RIPRAP SHALL BE WELL GRADED FROM A MAX SIZE OF 24" TO 1" SPALLS SUITABLE TO FILL HOLES BETWEEN ROCKS


SECTION 1
FINE GRAINED SILTY CLAY MATERIAL (CL-ML)
REPRESENTED BY FIELD SAMPLE NO 2011 FROM TP 201 (3' TO 4') BORROW "B" (3' TO 4')

SECTION 2
SILTY SAND MATERIAL (SM)
REPRESENTED BY FIELD SAMPLE NO 1001 (2' TO 2.7') FROM TP 100 TO BORROW "B" (3' TO 4')



TYPICAL SECTION OF RIPRAP & BEDDINGS WHEN UPSTREAM SLOPE CONSISTS OF SECTION 2 MATERIAL

GRAIN SIZE DISTRIBUTION GRAPH	
GRAIN SIZE IN MILLIMETERS	PERCENT FINER BY DRY WEIGHT
20	100
40	100
60	100
80	100
100	100
125	100
150	100
175	100
200	100
250	100
300	100
350	100
400	100
450	100
500	100
600	100
750	100
1000	100
1250	100
1500	100
2000	100
2500	100
3000	100
3500	100
4000	100
4500	100
5000	100
6000	100
7500	100
10000	100
12500	100
15000	100
20000	100
25000	100
30000	100
35000	100
40000	100
45000	100
50000	100
60000	100
75000	100
100000	100
125000	100
150000	100
200000	100
250000	100
300000	100
350000	100
400000	100
450000	100
500000	100
600000	100
750000	100
1000000	100
1250000	100
1500000	100
2000000	100
2500000	100
3000000	100
3500000	100
4000000	100
4500000	100
5000000	100
6000000	100
7500000	100
10000000	100
12500000	100
15000000	100
20000000	100
25000000	100
30000000	100
35000000	100
40000000	100
45000000	100
50000000	100
60000000	100
75000000	100
100000000	100
125000000	100
150000000	100
200000000	100
250000000	100
300000000	100
350000000	100
400000000	100
450000000	100
500000000	100
600000000	100
750000000	100
1000000000	100
1250000000	100
1500000000	100
2000000000	100
2500000000	100
3000000000	100
3500000000	100
4000000000	100
4500000000	100
5000000000	100
6000000000	100
7500000000	100
10000000000	100
12500000000	100
15000000000	100
20000000000	100
25000000000	100
30000000000	100
35000000000	100
40000000000	100
45000000000	100
50000000000	100
60000000000	100
75000000000	100
100000000000	100
125000000000	100
150000000000	100
200000000000	100
250000000000	100
300000000000	100
350000000000	100
400000000000	100
450000000000	100
500000000000	100
600000000000	100
750000000000	100
1000000000000	100
1250000000000	100
1500000000000	100
2000000000000	100
2500000000000	100
3000000000000	100
3500000000000	100
4000000000000	100
4500000000000	100
5000000000000	100
6000000000000	100
7500000000000	100
10000000000000	100
12500000000000	100
15000000000000	100
20000000000000	100
25000000000000	100
30000000000000	100
35000000000000	100
40000000000000	100
45000000000000	100
50000000000000	100
60000000000000	100
75000000000000	100
100000000000000	100
125000000000000	100
150000000000000	100
200000000000000	100
250000000000000	100
300000000000000	100
350000000000000	100
400000000000000	100
450000000000000	100
500000000000000	100
600000000000000	100
750000000000000	100
1000000000000000	100
1250000000000000	100
1500000000000000	100
2000000000000000	100
2500000000000000	100
3000000000000000	100
3500000000000000	100
4000000000000000	100
4500000000000000	100
5000000000000000	100
6000000000000000	100
7500000000000000	100
10000000000000000	100
12500000000000000	100
15000000000000000	100
20000000000000000	100
25000000000000000	100
30000000000000000	100
35000000000000000	100
40000000000000000	100
45000000000000000	100
50000000000000000	100
60000000000000000	100
75000000000000000	100
100000000000000000	100
125000000000000000	100
150000000000000000	100
200000000000000000	100
250000000000000000	100
300000000000000000	100
350000000000000000	100
400000000000000000	100
450000000000000000	100
500000000000000000	100
600000000000000000	100
750000000000000000	100
1000000000000000000	100
1250000000000000000	100
1500000000000000000	100
2000000000000000000	100
2500000000000000000	100
3000000000000000000	100
3500000000000000000	100
4000000000000000000	100
4500000000000000000	100
5000000000000000000	100
6000000000000000000	100
7500000000000000000	100
10000000000000000000	100
12500000000000000000	100
15000000000000000000	100
20000000000000000000	100
25000000000000000000	100
30000000000000000000	100
35000000000000000000	100
40000000000000000000	100
45000000000000000000	100
50000000000000000000	100
60000000000000000000	100
75000000000000000000	100
100000000000000000000	100
125000000000000000000	100
150000000000000000000	100
200000000000000000000	100
250000000000000000000	100
300000000000000000000	100
350000000000000000000	100
400000000000000000000	100
450000000000000000000	100
500000000000000000000	100
600000000000000000000	100
750000000000000000000	100
1000000000000000000000	100
1250000000000000000000	100
1500000000000000000000	100
2000000000000000000000	100
2500000000000000000000	100
3000000000000000000000	100
3500000000000000000000	100
4000000000000000000000	100
4500000000000000000000	100
5000000000000000000000	100
6000000000000000000000	100
7500000000000000000000	100
10000000000000000000000	100
12500000000000000000000	100
15000000000000000000000	100
20000000000000000000000	100
25000000000000000000000	100
30000000000000000000000	100
35000000000000000000000	100
40000000000000000000000	100
45000000000000000000000	100
50000000000000000000000	100
60000000000000000000000	100
75000000000000000000000	100
100000000000000000000000	100
125000000000000000000000	100
150000000000000000000000	100
200000000000000000000000	100
250000000000000000000000	100
300000000000000000000000	100
350000000000000000000000	100
400000000000000000000000	100
450000000000000000000000	100
500000000000000000000000	100
600000000000000000000000	100
750000000000000000000000	100
1000000000000000000000000	100
1250000000000000000000000	100
1500000000000000000000000	100
2000000000000000000000000	100
2500000000000000000000000	100
3000000000000000000000000	100
3500000000000000000000000	100
4000000000000000000000000	100
4500000000000000000000000	100
5000000000000000000000000	100
6000000000000000000000000	100
7500000000000000000000000	100
10000000000000000000000000	100
12500000000000000000000000	100
15000000000000000000000000	100
20000000000000000000000000	100
25000000000000000000000000	100
30000000000000000000000000	100
35000000000000000000000000	100
40000000000000000000000000	100
45000000000000000000000000	100
50000000000000000000000000	100
60000000000000000000000000	100
75000000000000000000000000	100
100000000000000000000000000	100
125000000000000000000000000	100
150000000000000000000000000	100
200000000000000000000000000	100
250000000000000000000000000	100
300000000000000000000000000	100
350000000000000000000000000	100
400000000000000000000000000	100
450000000000000000000000000	100
500000000000000000000000000	100
600000000000000000000000000	100
750000000000000000000000000	100
1000000000000000000000000000	100
1250000000000000000000000000	100
1500000000000000000000000000	100
2000000000000000000000000000	100
2500000000000000000000000000	100
3000000000000000000000000000	100
3500000000000000000000000000	1




B-31





10/12

THE LOWER SPURT SECTION WILL BE EXCAVATED AS NEARLY TO GRADE AS THE SKILLFUL OPERATION OF EXCAVATING EQUIPMENT, INCLUDING A ROCK RIPPER ATTACHMENT, WILL PERMIT. SATISFACTORY EVIDENCE WITHIN THE LIMITS OF THIS PLANT SHALL BE DETERMINED BY THE ENGINEER. THE SECTION FROM STA 2+70 TO 3+20 (APPROX) SHALL BE SUCH SO THAT ALL POINTS ARE AT LEAST 18" TO 24" ABOVE THE LOWER SPURT BOTTLE. THE SECTION FROM STA 3+20 TO 4+00 SHALL BE SUCH AS TO COMPLY WITH THE PRINCIPAL SPURT. AFTER COMPLETION OF ROUGH ETC, IN THE 30' HIGH SECTION DESCRIBED ABOVE, THE ENTIRE SECTION SHALL BE THOROUGHLY FLUSHED WITH WATER TO REMOVE ALL DIRT & LOOSE ROCK PARTICLES. ALL CRACKS & DEFECTS SHALL BE CLEANED OUT AS SET FORTH IN SPECIFICATION NOS 4 AND 5. THE CONTROL SECTIONS OF THE LOWER & PRINCIPAL SPURTS WILL BE SHAPED SYMMETRICALLY WITH CLASS 3000 CONCRETE AS DIRECTED BY THE ENG. TO FORM A UNIFORM CREST SECTION. HIGH SLUMP CONCRETE WILL BE

USED TO FILL CRACKS AND DEFECTS WHILE LOW SLUMP UNREINFORCED CONCRETE WILL BE USED TO SHAPE THE CREST SECTION. PAYMENT WILL BE MADE AT THE CONTRACT UNIT PRICE FOR CUBIC YARD AS MEASURED AT THE MIXING PLANT.




NOTE: UNLESS OTHERWISE DIRECTED BY THE ENGINEER, THE DIKE CUTOFF TRENCH SHALL BE EXCAVATED A MINIMUM OF 4 FT BELOW NATURAL GRADE.




BLODGETT POND WHITE RIVER R.C. AND D. PROJECT BRADFORD, VERMONT PROFILES	
U. S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE	
J. H. BRYANT Designer Date: May '65	Approved by: [Signature] Date: May '65
Checked: H. J. BRYANT Date: May '65	Drawn: [Signature] Date: May '65
Project: [Signature] Date: May '65	
Form 5 10	
VT-	

NOT TO SCALE
B-30


2 of 2



PROFILE ALONG E OF PRINCIPAL AND EMERGENCY



TYPICAL SECTION OF PRINCIPAL & EMERGENCY SPILLWAY



PROFILE ALONG E OF POND DRAIN

Am.

THE SULLIVAN QUARRY AND CONTROL SECTION ALIGNMENT MAY BE ADJUSTED TO MINIMIZE OVER ELEVATION THE LOCATION OF THE CONTROL SECTION CONTAINING WALL AND MAIN AS SHOWN FOR THE QUARRY WILL BE RECONSTRUCTED TO THE 100 PER SULLIVAN LEVEL. NO CHANGES IN THE SULLIVAN QUARRY CHANNELS WILL BE NECESSARY AND A MINIMUM OF 100 PER SULLIVAN/REAR FACING CONTROL SECTION. THE LOCATION OF THE REAR FACING, 60 PER SULLIVAN & 60 PER 6000 WILL BE SHOWN AS SHOWN

Return Note

LINK TO AM 17 6 3

80) POWERS/MIN OF N

160 POUNDS/ALIVE OF AQ


EX: ROUNDS/4 AM OF H₂O

10 ROUNDS / 4 LBS OF FLEO POP

10 POUNDS, MAKE BEN/UMT BLUE GRASS

K. IVUMOS' ARE EMANE INEE POW

PAUL M. C. DIER



**BLODGETT POND
WHITE RIVER R.C. AND D. PROJECT
BRADFORD, VERMONT
PLAN OF DAMSITE**

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

J. M. BRYANT J. M. BRYANT J. M. BRYANT J. M. BRYANT J. M. BRYANT J. M. BRYANT	Feb. 68 May '68 Feb. 68 May '68 May '68 May '68	Received by _____ _____ _____ _____ _____ _____
L. M. BRYANT L. M. BRYANT	May '68 May '68	Sent to _____ _____ _____ _____ _____ _____

EMERGENCY SPILLWAY

CURVE DATA

CURVE I

STATION	DEFLECTION	CHORD
DC = 3+00	0	0
2+75	4° 29'	24.91
2+50	8° 57'	24.91
2+25	13° 26'	24.91
2+00	17° 54'	24.91
PT = 1+85.55	20° 51'	16.45

$\Delta = 41^\circ - 42'$
 $R = 160'$
 $D = 35.81'$
 $T = 60.94'$
 $E = 11.19'$
 $M = 10.46'$
 $L = 116.45'$

CURVE II


STATION	DEFLECTION	CHORD
PC = 3+00	0	0
2+75	8° 35'	24.98
2+50	17° 10'	24.98
2+25	25° 45'	24.98
2+00	34° 19'	24.98
1+75	42° 54'	24.98
1+50	51° 29'	24.98
PT = 1+94.21	59° 43'	15.79

$\Delta = 41^\circ - 50'$
 $R = 200'$
 $D = 28.65'$
 $T = 88.00'$
 $E = 18.50'$
 $M = 16.93'$
 $L = 165.79'$

CURVE III

STATION	DEFLECTION	CHORD
PC = 3+00	0	0
2+75	7° 16'	25.00
2+50	14° 29'	25.00
2+25	21° 43'	25.00
2+00	28° 57'	25.00
1+75	36° 11'	25.00
1+50	43° 26'	25.00
1+25	50° 40'	25.00
1+00	57° 54'	25.00
0+75	65° 9'	25.00
PT = 0+56.98	71° 45'	18.02

$\Delta = 45^\circ - 38'$
 $R = 320'$
 $D = 17.90'$
 $T = 127.61'$
 $E = 24.48'$
 $M = 27.74'$
 $L = 249.02'$





(1) Primary/Secondary Spillway Crest Wall,
Showing Eroded Section. Bedrock in Back-
ground is Left Abutment of Dam.



(2) Reinforced Concrete Sill
Extension at Right End of
Spillway

U.S. ARMY ENGINEER DIV, NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

JAMES W. SEWALL COMPANY
CONSULTANTS
OLD TOWN, MAINE


NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

Blodgett Dam

VT 00117

Bradford, Vermont

April 22, 1980



(3) Upstream Slope of Dam From Spillway Channel Entrance.



(4) Crest of Dam, Looking Toward Right Abutment.

U.S. ARMY ENGINEER DIV, NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

JAMES W. SEWALL COMPANY
CONSULTANTS
OLD TOWN, MAINE

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

Blodgett Dam

VT 00117

Bradford, Vermont

April 22, 1980

C-3



(5) Downstream Slope, from Point Near Right Abutment.



(6) Low Level Outlet at Toe of Dam.

U.S. ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

JAMES W. SEWALL COMPANY
CONSULTANTS
OLD TOWN, MAINE

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS


Blodgett Dam

VT00117

Bradford, Vermont

April 22, 1980

C-4



(7) Seepage Immediately Downstream of Drainage Outlet Pipe.



(8) Pool Downstream of Seepage in Photo (7).

U.S. ARMY ENGINEER DIV, NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

JAMES W. SEWALL COMPANY
CONSULTANTS
OLD TOWN, MAINE

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS


Blodgett Dam

VT 00117

Bradford, Vermont

April 22, 1980

C-5



(9) Partial View of Extensive Area of Seepage in Original Ground Below Toe of Dam.



(10) Seepage Exiting Original Ground at Base of Tree.

U.S. ARMY ENGINEER DIV, NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

JAMES W. SEWALL COMPANY
CONSULTANTS
OLD TOWN, MAINE

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

Blodgett Dam
VT 00117
Bradford, Vermont
April 22, 1980

C-6



(11) Animal Burrow Near Toe of Dam.



(12) Low Level Outlet Gate Housing.

U.S. ARMY ENGINEER DIV, NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

JAMES W. SEWALL COMPANY
CONSULTANTS
OLD TOWN, MAINE

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

Blodgett Dam
VT 00117

Bradford, Vermont

April 22, 1980



(13) Low Level Outlet Channel.



(14) Spillway Channel, From Primary/Secondary Spillway Crest.

U.S. ARMY ENGINEER DIV, NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

JAMES W. SEWALL COMPANY
CONSULTANTS
OLD TOWN, MAINE

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS


Blodgett Dam

VT 00117

Bradford, Vermont

April 22, 1980

C-8



(15) Roadway Across Spillway Channel.



(16) Spillway Channel Downstream of Road Crossing.

U.S. ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

JAMES W. SEWALL COMPANY
CONSULTANTS
OLD TOWN, MAINE

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS


Blodgett Dam

VT 00117

Bradford, Vermont

April 22, 1980

C-9



(17) Erosion of Right Side of Spillway Channel.



(18) November 4, 1927 Flood Level Marker (Disk) on Backwall of B & M Railroad Bridge Crossing Roaring Brook.

U.S. ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS


JAMES W. SEWALL COMPANY
CONSULTANTS
OLD TOWN, MAINE


NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS


Blodgett Dam
VT 00117
Bradford, Vermont
April 22, 1980

C-10

APPENDIX D
HYDRAULIC/HYDROLOGIC COMPUTATIONS







Subject Hydrology / Hydrology / Hydrology

Computation Hydrology Job No. 952

Computed by WJH Checked by WJH/RW Date 8-2-58

Hydrology / Hydrology / Hydrology

I. Performance of the Flood Control

A. Maximum Probable Flood

a) Watershed: Chicopee at Springfield, Mass.
Area: 100 sq. mi. / 17.5 sq. mi. / 100 sq. mi.

b) Watershed: Area
3.70 sq. mi. / 1.1 sq. mi. / 1.1 sq. mi.
3.85 sq. mi. / 1.1 sq. mi. / 1.1 sq. mi.

c) Flow: NE. Area: 1.1 sq. mi. / 1.1 sq. mi. / 1.1 sq. mi.
Flow: 1.1 sq. mi. / 1.1 sq. mi. / 1.1 sq. mi.

PMF: 1.1 sq. mi. / 1.1 sq. mi. / 1.1 sq. mi.

PMF: 1.1 sq. mi. / 1.1 sq. mi. / 1.1 sq. mi.

PMF: 1.1 sq. mi. / 1.1 sq. mi. / 1.1 sq. mi.

d) Peak Flow

Peak flow: 1.1 sq. mi. / 1.1 sq. mi. / 1.1 sq. mi.
Peak flow: 1.1 sq. mi. / 1.1 sq. mi. / 1.1 sq. mi.

Peak flow: 1.1 sq. mi. / 1.1 sq. mi. / 1.1 sq. mi.

Peak flow: 1.1 sq. mi. / 1.1 sq. mi. / 1.1 sq. mi.

II. Flood Control

Flow: 1.1 sq. mi. / 1.1 sq. mi. / 1.1 sq. mi.

Flow: 1.1 sq. mi. / 1.1 sq. mi. / 1.1 sq. mi.

Flow: 1.1 sq. mi. / 1.1 sq. mi. / 1.1 sq. mi.

Flow: 1.1 sq. mi. / 1.1 sq. mi. / 1.1 sq. mi.

Flow: 1.1 sq. mi. / 1.1 sq. mi. / 1.1 sq. mi.

Flow: 1.1 sq. mi. / 1.1 sq. mi. / 1.1 sq. mi.

AD-A157 558

NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
BLODGETT DAM (VT 0011) (U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV OCT 80

2/2

UNCLASSIFIED

F/G 13/13


NL



END

FORMED

DTIC



MICROCOPY RESOLUTION TEST CHART
 NBS-1963-A

12-23-65 MB

3-65 FHW

DODGETT POND

STGE-STAGE CURVE

200

195

190

185

180

175

170

165

160

EL. 185.0 EMS CREST

EL. 184.0 N.W.L.

98.7 AF

113 AF

EL. 191.2 DAW

210.5 AF

EL. 195.2 TOP OF DAM

218.6 AF

NOTE: CORRECTION FOR VOLUME OF
DAM INCLUDED

STORAGE - ACRE FEET

Subject Inspection of ~~new~~ flood control dam

Computation Blodgett Dam

Job No. 953-05 L

Computed by NEE

Checked by SDM/BW

Date 8-28-20

i) SIZE cont.

Storage cont.

Note that elevations used on the stage-storage curve are from the S.C. Conservation Service datum. Approximate equation is $SCS + 960 = NGVD$.

Height = 29.9 feet - $\frac{1}{4}$ Dept. of Water Resources Information Sheet

ii) Hazard Potential

U.S. Rd. 1 crosses Abundant Brook approx 3466 feet elevation on the river side and the Eastern Abundant R.P. crosses approximately 150 feet elevation. Both these structures would be overtopped causing severe damage. Due to the nature of the A few trees could be lost at log camp south of dam.

iii) Classification

SIZE : SMALL

HAZARD : SIGNIFICANT

iv) Test Flood = 100 year flood = $\frac{1}{5}$ PMF = 1600 cfs
(used "Ratio of Probable Maximum 6-Hour Precipitation for 10 years. Also to 100-year 6-Hour PMF")
given in the Dept. of Comm. Tech. Rep. #10, p. 58.

Subject Impacts of non-flooded dams

Computation Bligh's Dam Job No. 980-152

Computed by MEP Checked by SDM/BW Date 8-28-80

3) Surcharge at East Tailrace

a) Peak Inflow

Peak Flood = 1600 cfs @ 100 yr. flood

b) Outflow Rating Curve

Primary Spillway el. 649 MSLD L=15' width=7'

$$Q = C H^{3/2} \quad C = 2.85$$

* A 3 foot long section of this spillway had been severely damaged, no correction was made for this in the flow calculations

H	MSL	Q
1	645.0	43
2	646.0	121
4	648.0	342
6	650.0	623
8	652.0	947
10	654.0	1352
11.2	655.0	1600

Emergency Spillway el. 645 MSLD L=65' width=7'

$$Q = C H^{3/2} \quad C = 2.85$$

H	Q	MSL	H	Q	MSL
1	135	646.0	7	3431	652.0
3	947	648.0	9	4782	654.0
4	2071	650.0	10.2	6035	655.0

Right Side of Emergency Spillway

$$Q = C H^{3/2} \quad C = 2.85$$

$$Q = C H^{3/2} \quad C = 2.85$$

H	Q	MSL	H	Q	MSL
1	5	646.0	2	22	648.0
3	45	648.0	4	112	650.0
5	141	650.0	6	270	652.0

Subject Inspection of ...

Computation ... Job No. ...

Computed by ... Checked by SDH / BW Date ...

18" ...
 $Q = 60 \text{ cfs}$

Left Side of Emergency Spillway

Side Slope = 1.5 H to 1 V

$Q = CLH^{2.2}$ $C = 2.5$ stepping in 1 ft vertical increments

H (ft)	Q	WS EL	H (ft)	Q	WS EL
1	4	646.0	7	230	652.0
3	34	648.0	9	415	654.0
5	106	651.0	10.2	561	655.2

The outflow rating curve is plotted on page 6

a) Spillway Capacity to Top of Dam

$Q_s = 8950 \text{ cfs}$ WS EL = 655.2

$Q_s = 559$ % of the Test Max $Q_p = 1600 \text{ cfs}$

d) Surge Height to Pass Q_p

$Q_p @ 100 \text{ yr flood} = 1600 \text{ cfs}$

(see curve p. 6)

$H = 648.3 - 644.0 = 4.3'$

4) Effect of Surge on Max Probable Discharge

a) Pond Area - varies with surge (see curve p. 7)

(Curve from Unit Flood, R.R. & D. ...)

Draw Pond ...

or for ...

6) ... Normal Pool Level at ...

644.0 MSL

... 3.1 ...

Subject Inspection of non-federal dams

Computation Blodgett Dam

Job No. 253-051


Computed by MSE

Checked by

SDM/BW


Date

8-29-80



1-23-65 JMS
3-65 F.M.V.
KIDGETT POND

STAGE-AREA CURVE



NOTE CORRECTION FOR
VOLUME OF DAM
INCLUDED

Computation Plotting Data

Job No. 902-051

Computed by nsf

Checked by _____

CDL / R.W

Date 7-1-50

H = 3.5'
= 647.5 N
= 187.5

$$V = 152 - 98.7 = 53.3 \text{ Acft} \quad (\text{Quar. pr.})$$

53.3	=	0.27''
------	---	--------

37104.2

$$H = 4.5$$

$$V = 171,0 - 98,7 = 72,3 \text{ Ac-ft}$$

548.5 N' 12
188.5

$$5 \div 12.3 = 0.37''$$

3. 1159.2

Geoffrey's father, Dr. W. H. F. F. F.

100 yr flood $C_{100} = C_{10} \cdot 1.38$

3.5

$$Q_1 = 1600 \cdot (1 - \frac{.27}{3.8}) = 1480 \text{ cfs}$$

H 4.5

$$Q_p = 1600 \left(1 - \frac{.37}{3.8} \right) = 1440 \text{ cfs}$$

c) Red. Outflow (Q_o)

[illegible]

Four 1/2" Aluminum Plates

1470

$$H = 4.2$$

51 Sylvania Company, 20, 2011

Quadrado de 70 cm x 90 cm

109 7-

Subject _____

Computation _____ Job No. _____

Computed by _____ Checked by SDM/BW Date 9-4-80

5) Summary

a) Peak Inflow

$Q_p = 1600$ cfs = Test Flood @ 100 yr flood

b) Peak Outflow

$Q_p = 1470$ cfs

c) Spillway Max Capacity

$Q = 2950$ cfs or 60% of Q_p

At Test Flood = 100 yr flood, the spillway
handles the runoff flow utilizing $\pm 16\%$ of its capacity
with an average surcharge above the spillway
crest of 4.2 ft and 6.8 feet below the top
of the dam.

Subject Design of non-federal dam

Computation Plumb Dam

Job No. 753-151

Computed by H. E.

Checked by S. H.

Date 7-7-80

II. Downstream Tailwater Hazard

a) Peak Flood Outflow

a) Breach Outflow

Mid-Height Elev. = 610.5 NGVD

Approx. Mid-Height Length = 230' (from SCS formula)

Breach Width (from NED-AGE Dam Failure Guidelines)

$$W_b = 0.4 \times 230 = 92 \text{ Feet}$$

Height at time of failure $h_b = 29.4 \text{ feet}$

$$\text{Breach Outflow} = Q_b = \frac{9}{27} W_b \sqrt{h_b} \quad \begin{matrix} W_b = 92 \\ h_b = 29.4 \\ g = 32.2 \end{matrix}$$

$$Q_b = 24,650 \text{ cfs}$$

b) Remaining Spillway Discharge

Since the breach is assumed to occur in the center of the spillway, the remaining spillway discharge is assumed to be equal to the capacity of the top of the dam.

Fig. 3-12, SCS

3. The remaining discharge is assumed to be equal to the capacity of the top of the dam.

4. The remaining discharge is assumed to be equal to the capacity of the top of the dam.

5. The remaining discharge is assumed to be equal to the capacity of the top of the dam.

6. The remaining discharge is assumed to be equal to the capacity of the top of the dam.

Subject Design of Sewerage System for Town of Old Town, Maine

Computation for Sewerage System Job No. 100-100


Computed by J. W. Sewall Checked by J. W. Sewall Date 10/1/10

5) Peak Day Flow Rate Estimated from Census Data

Peak Day Flow Rate = 1.15 x 1000 = 1150 gpd Reach = 1

Peak Hour Flow Rate = 1150 gpd / 24 hr = 47.9 gpd

Required Pipe Diameter: $V = 1.48 R^{2/3} S^{1/2}$ $Q = AV$ 59.09



6' 17.5' - 17.5' - 17.5' - 17.5'

Depth of Sewer = 17.5' Depth of

Highways Center Line C.I. = 5 feet

11 = 10 12 = 10 13 = 10 14 = 10 15 = 10 16 = 10 17 = 10 18 = 10 19 = 10 20 = 10

Design of Sewerage System

Station	A	P	F	V	Q
1	4"	12.5	14.3	14.3	57.2
2	12"	50.0	60.0	60.0	150.0
3	18"	112.5	135.0	135.0	425.0
4	24"	200.0	240.0	240.0	720.0
5	30"	300.0	360.0	360.0	1080.0
6	36"	400.0	480.0	480.0	1440.0
7	42"	500.0	600.0	600.0	1800.0
8	48"	600.0	720.0	720.0	2160.0
9	54"	700.0	840.0	840.0	2520.0
10	60"	800.0	960.0	960.0	2880.0

Design of Sewerage System

Station	A	P	F	V	Q
1	12"	50.0	60.0	60.0	150.0
2	18"	112.5	135.0	135.0	425.0
3	24"	200.0	240.0	240.0	720.0
4	30"	300.0	360.0	360.0	1080.0
5	36"	400.0	480.0	480.0	1440.0

Subject T. ...

Computation ... Job No. 7700-1000

Computed by P. P. Checked by SDM Date 1. 2. 19...

1	2	3	4	5	6
1.2	1.2	1.2	1.2	5.75	1.2
1.2	1.2	1.2	1.2	5.75	1.2
1.2	1.2	1.2	1.2	5.75	1.2
1.2	1.2	1.2	1.2	5.75	1.2
1.2	1.2	1.2	1.2	5.75	1.2

... of ...

... = 16.50 ...

... (1.2 x 1.2 x 1.2)

... = 5.75 ...

... = 10.25 ...

... = 1.29 ...

... = 9.43 ...

... = 22.00 ... H = 12.1"

... = 1.25 ...

... = 32.25 ...

... = 1.25 ...

2) ...

... Remainder

...

...

...

...

...

...

...

...

...

...

...


...

...

Subject Truss

Computation for Job No. 7-10-0


Computed by W. S. Checked by SPY Date 7-10-0



NOT AVAILABLE AT THIS TIME

APPENDIX E
INFORMATION AS CONTAINED IN
THE NATIONAL INVENTORY OF DAMS

"RULE OF THUMB" GUIDANCE FOR ESTIMATING DOWNSTREAM DAM FAILURE HYDROGRAPHS



STEP 1: DETERMINE OR ESTIMATE RESERVOIR STORAGE (S) IN AC-FT AT TIME OF FAILURE.

STEP 2: DETERMINE PEAK FAILURE OUTFLOW (Q_{p1}).

$$Q_{p1} = \frac{8}{27} W_b \sqrt{Y_0}^{3/2}$$

W_b = BREACH WIDTH - SUGGEST VALUE NOT GREATER THAN 40% OF DAM LENGTH ACROSS RIVER AT MID HEIGHT.

Y_0 = TOTAL HEIGHT FROM RIVER BED TO POOL LEVEL AT FAILURE.

STEP 3: USING USGS TOPO OR OTHER DATA, DEVELOP REPRESENTATIVE STAGE-DISCHARGE RATING FOR SELECTED DOWNSTREAM RIVER REACH.

STEP 4: ESTIMATE REACH OUTFLOW (Q_{p2}) USING FOLLOWING ITERATION.

A. APPLY Q_{p1} TO STAGE RATING, DETERMINE STAGE AND ACCOMPANYING VOLUME (V_1) IN REACH IN AC-FT. (NOTE: IF V_1 EXCEEDS $1/2$ OF S, SELECT SHORTER REACH.)

B. DETERMINE TRIAL Q_{p2} .

$$Q_{p2}(\text{TRIAL}) = Q_{p1} \left(1 - \frac{V_1}{S}\right)$$

C. COMPUTE V_2 USING Q_{p2} (TRIAL).


D. AVERAGE V_1 AND V_2 AND COMPUTE Q_{p2} .

$$Q_{p2} = Q_{p1} \left(1 - \frac{V_1 + V_2}{2S}\right)$$

STEP 5: FOR SUCCEEDING REACHES REPEAT STEPS 3 AND 4.

APRIL 1978

ESTIMATING EFFECT OF SURCHARGE STORAGE ON MAXIMUM PROBABLE DISCHARGES



STEP 1: Determine Peak Inflow (Q_{p1}) from Guide Curves.

STEP 2: a. Determine Surcharge Height To Pass " Q_{p1} ".

b. Determine Volume of Surcharge ($STOR_1$) In Inches of Runoff.

c. Maximum Probable Flood Runoff In New England equals Approx. 19", Therefore:

$$Q_{p2} = Q_{p1} \times \left(1 - \frac{STOR_1}{19}\right)$$

STEP 3: a. Determine Surcharge Height and " $STOR_2$ " To Pass " Q_{p2} "

b. Average " $STOR_1$ " and " $STOR_2$ " and Determine Average Surcharge and Resulting Peak Outflow " Q_{p3} ".

3000

2500

2000

1500

1000

500


0

M.P.F. IN C.F.S./SQ. MILE

42-0

MAXIMUM PROBABLE FLOOD PEAK FLOW RATES

x5 - NED DAM IDENTIFICATION
⊗ 7' - TWICE SPF AT INDICATED SITES
DEC. 1977



MAXIMUM PROBABLE FLOWS
BASED ON TWICE THE
STANDARD PROJECT FLOOD
(Flat and Coastal Areas)

<u>River</u>	<u>SPF</u> (cfs)	<u>D.A.</u> (sq. mi.)	<u>MPF</u> (cfs/sq. mi.)
1. Pawtuxet River	19,000	200	190
2. Mill River (R.I.)	8,500	34	500
3. Peters River (R.I.)	3,200	13	490
4. Kettle Brook	8,000	30	530
5. Sudbury River.	11,700	86	270
6. Indian Brook (Hopk.)	1,000	5.9	340
7. Charles River.	6,000	184	65
8. Blackstone River.	43,000	416	200
9. Quinebaug River	55,000	331	330

MAXIMUM PROBABLE FLOOD INFLOWS
NED RESERVOIRS

<u>Project</u>	<u>Q</u> (cfs)	<u>D.A.</u> (sq. mi.)	<u>MPF</u> cfs/sq. mi.
1. Hall Meadow Brook	26,600	17.2	1,546
2. East Branch	15,500	9.25	1,675
3. Thomaston	158,000	97.2	1,625
4. Northfield Brook	9,000	5.7	1,580
5. Black Rock	35,000	20.4	1,715
6. Hancock Brook	20,700	12.0	1,725
7. Hop Brook	26,400	16.4	1,610
8. Tully	47,000	50.0	940
9. Barre Falls	61,000	55.0	1,109
10. Conant Brook	11,900	7.8	1,525
11. Knightville	160,000	162.0	987
12. Littleville	98,000	52.3	1,870
13. Colebrook River	165,000	118.0	1,400
14. Mad River	30,000	18.2	1,650
15. Sucker Brook	6,500	3.43	1,895
16. Union Village	110,000	126.0	873
17. North Hartland	199,000	220.0	904
18. North Springfield	157,000	158.0	994
19. Ball Mountain	190,000	172.0	1,105
20. Townshend	228,000	106.0(278 total)	820
21. Surry Mountain	63,000	100.0	630
22. Otter Brook	45,000	47.0	957
23. Birch Hill	88,500	175.0	505
24. East Brimfield	73,900	67.5	1,095
25. Westville	38,400	99.5(32 net)	1,200
26. West Thompson	85,000	173.5(74 net)	1,150
27. Hodges Village	35,600	31.1	1,145
28. Buffumville	36,500	26.5	1,377
29. Mansfield Hollow	125,000	159.0	786
30. West Hill	26,000	28.0	928
31. Franklin Falls	210,000	1000.0	210
32. Blackwater	66,500	128.0	520
33. Hopkinton	135,000	426.0	316
34. Everett	68,000	64.0	1,062
35. MacDowell	36,300	44.0	825

PRELIMINARY GUIDANCE
FOR ESTIMATING
MAXIMUM PROBABLE DISCHARGES
IN
PHASE I DAM SAFETY
INVESTIGATIONS

New England Division
Corps of Engineers

March 1978

Subject Improvement of Port-land Ave.

Computation Blodgett's Job No. 1234567

Computed by L.S. Checked by SM Date 9-15-57

Summary

a) Peak Failure Out-Flow $Q_p \approx 33,000 \text{ cfs}$

b) Rise in Stage = 300 ft Dia of Dam @ Warden Co.
Pre-failure stage = 6.75 feet
Failure stage = 10.07 feet
Rise in stage = $10.07 - 6.75 = 3.32 \text{ feet}$


c) Rise in Stage = 300 ft Dia of Dam
Pre-failure stage = 8.9 feet
Failure stage = 12.2 feet
Rise in stage = $12.2 - 8.9 = 3.3 \text{ feet}$
U.S. Army Corps of Engineers
by 3.3 feet of water in the reservoir

d) Rise in Stage = 300 ft Dia of Dam
Pre-failure stage = 11.75 feet
Failure stage = 14.7 feet
Rise in stage = $14.7 - 11.75 = 2.95 \text{ feet}$
Rise in stage = 11.75 feet
with 1000 ft of water in the reservoir
which is 1000 ft of water in the reservoir

Subject Water Surface Elevation of Dam

Computation by J. W. Sewall Job No. 252-1-11

Computed by J. W. Sewall Checked by SDM Date 9-15-80




Subject Intermittent Sewerage System - Old Town, Maine

Computation Flow in Sewer Job No. 10-1-10

Computed by J. W. S. Checked by S. M. S. Date 7-7-10

a) Section at Railroad Crossing: 200' x 100' x 100'



Manning $N = 0.0135$ $R^{2/3} = 8.74$ $V = 1.48$ $SE = 0.03$
 $Q = 1.48 \times 8.74 \times 1.48 = 19.5$

H	A	P	R	V	Q
2	1.0	37	1.75	0.46	0.87
4	1.5	41	2.22	0.68	1.65
6	1.9	44	2.44	0.78	2.42
8	2.4	47	2.67	0.87	3.21
10	2.9	50	2.88	0.95	4.17
12	3.4	52	3.07	1.02	5.27
13	4.0	53	3.24	1.07	6.27

Flow capacity changed in Sewer due to pipe size

Flow over the Bottom of Manhole at Tracks

$Q = CLH^{3/2}$ $C = 2.48$ $L = 750' + 400' = 1150'$

H	Q
1	8375 cfs
1.5	13150 cfs
1.8	17100 cfs

Subject Flowage of Lake Umbagog


Computation Flowage of Lake Umbagog Job No. 752-1-1

Computed by W. J. Sewall Checked by W. J. Sewall Date 9-12-23

Rating at failure flow through Reservoir #2 at 12.5 ft

$$Q_p = 33000 \text{ cfs} \left(\frac{19.3 - 12.5}{27.5} \right)^{1.5} = 20287 \text{ cfs say } 30000 \text{ cfs}$$

Downstream (12.5 - 70 ft) of Reservoir #2 X-section shown:



$$V_1 = 12.5 - 8.9 = 3.6 \text{ feet}$$

$$Q_p \text{ (Hill) } = 33000 \left(\frac{19.3 - 8.9}{27.5} \right)^{1.5} = 20287 \text{ cfs}$$

$$V_2 = 12.5 - 8.9 = 3.6 \text{ feet}$$

$$Q_p = 33000 \left(\frac{19.3 - 8.9}{27.5} \right)^{1.5} = 20287 \text{ cfs say } 22500 \text{ cfs}$$

Failure stage at Route 5 crossing Free curve

$$Q_p = 29500 \text{ cfs } H = 19.3 \text{ feet}$$

$$\text{Rise in stage} = 19.3 - 8.9 = 10.4 \text{ feet}$$

Failure flow will overflow roadway
by 5.3 feet.

③ Rise in stage at Railroad crossing approximately
10.4 feet due to failure of Reservoir #2

Pre-failure stage at RR crossing

Pre-failure stage at RR crossing

Pre-failure stage at RR crossing

$$Q_p = 59500 \text{ cfs } H = 11.75 \text{ feet}$$

Failure stage at RR crossing


$$Q_p = 59500 \text{ cfs } H = 19.70 \text{ feet}$$

$$\text{Failure stage} = 19.7 - 11.75 = 7.95 \text{ feet}$$

Subject Design of Sewerage System

Computation for 1000 People Job No. 1000

Computed by J. W. Sewall Checked by J. W. Sewall Date 7-1-12



Computed by 11/15 Checked by 2016 Date 1-1-1

D-15

END

FILMED

9-85

DTIC